

Mobile material storage for small to medium-sized projects

Features:

- Shelving system (height adjustable)
- Power connection: 220 / 380 Volt
- Main power connection outside 32A
- Interior lighting
- Wooden floor
- Forklift pockets
- Container corners
- Optional:
Indoor and outdoor castors
Trailer

Additional equipment:

- Shelves:
2.97 m x 0.72 m x 2.35 m,
5 inserts left and right,
Footprint for transport crates:
2.75 m x 0.6 m
- LED illumination
- Sockets inside: 3 x 230 V 1 x 16 A
- Adjustable table 1.05 m x 0.46 m
- Optional: two-level step (if using
container with castors)



Dimensions:

- Outside length: 2.99 m
- Inside length: 2.83 m
- Outside width: 2.44 m
- Inside width: 2.34 m
- Outside height: 2.59 m
- Inside height: 2.38 m

Weights:

- Tare weight: approx. 1,400 kg
- Payload: approx. 1,250 kg
- Permissible total weight (container and trailer): 3,500 kg
- Trailer weight (empty): 860 kg

AWH Material Container



Compared to the swap body, the material container is only **just under 3 meters long** and can be used more flexibly thanks to its compact dimensions and optional indoor or outdoor castors

– perfect for small to medium-sized projects or occasional withdrawals over a longer period of time.

The container moves to match the progress of the construction site, reducing travel times for the fitters.

Paint:
Outside: blue RAL 5010

